



Beaver County Service Centre
 5120 - 50 Street Box 140
 Ryley, Alberta T0B 4A0
 Monday to Friday
 8:30 a.m. - 4:30 p.m.

Phone: (780) 663-3730
 Fax: (780) 663-3602
 Toll Free: 1-866-663-1333
 www.beaver.ab.ca
 Email: administration@beaver.ab.ca

2018 Beaver County Road Construction



Construction Update: Terracem Projects

A light tac coat has been applied to Township Road 512 from Highway 834 to RR 191 (Creamery Road), and Range Road 191 (Creamery Road), south of TWP 512 to 53 Ave in Tofield, and is re-open for traffic and public use. Please exercise caution and observe traffic/construction signs when travelling these roads.

All Terracem cementing has been completed and now chip seal needs to be applied to achieve the hard surface. This is not asphalt, but the end result will seem similar to residents and the travelling public, and will result in roads that are not dusty when dry, nor muddy when wet.

The contractor will return in the next couple of weeks to apply the chip seal. Range Road 191 and Township Road 512 will receive the first lift. All other roads (Township Roads 492 and 510, and Range Road 201) will receive their 2nd lift and will be complete. Following this work, the contractor will return to Township Road 512 and Range Road 191 for the 2nd lift, and then those roads will be complete.

During this time, the roads may be closed to allow crews to work safely; however, access for local landowners will be maintained during construction. We encourage patrons to take alternate routes until the projects are complete.

There are potential hazards to the public and vehicles during the construction process. This can include heavy machinery, dust or mud, and road materials such as gravel, asphalt coatings, and rock chips. After the roads are stabilized, a coat of chip seal will be applied that can make your vehicle dirty.

Finally, there will be loose rock chips present for some time after application that can scratch your vehicle. The final chips will be brushed off after the surface has cured (generally after a few weeks).

Please be advised the speed limit will be 50 km/h while posted, as there will be crews on the road who need to work safely, and it will help keep the loose rock chips more stationary.

This schedule is weather dependent. Thank you for your patience and understanding during construction. If you have any questions, please call the Beaver County Service Centre at 780-663-3730.

Development Permit

The following Development Application has been APPROVED (except where otherwise noted) by the Development Officer under the provisions of Land Use Bylaw No. 98-801, subject to the right of appeal to the Subdivision and Development Appeal Board.

APPEAL DEADLINE: August 29, 2018

Application No. 020020-18-D0052

Applicant: Falk, Ryan
 Location: **Plan 782 2987; Block 1; Lot 12 in SE 34-50-20-W4**
 Development: Home Occupation Type 2: Bottled Water and Ice Business Using Reverse Osmosis in Existing Building

Any person wishing to appeal a decision may do so by serving written notice, on the prescribed form (stating reasons for the appeal) and submitting the applicable fee of \$200.00 to the Secretary of the Subdivision and Development Appeal Board at the following address.

The notice of appeal must be submitted or postmarked before 4:30 pm on the appeal deadline date shown above. The appeal prescribed form is available at www.beaver.ab.ca or at the County office.

Further information regarding the above decisions may be obtained from the County Office, Ryley, Alberta.

SECRETARY
 Subdivision and Development Appeal Board
 Beaver County
 Box 140 Ryley, Alberta T0B 4A0
 (780) 663-3730

2018 Construction Schedule

Task	Start Date	Working Days	Projected End Date	Update – August 8
Culvert Maintenance	Apr 24	135	Oct 30	
Twp 492 Terracem	Jun 11	15	Jun 29	Terracem is complete; 2 nd lift of chip seal to be applied by mid-August
Rge 201 Terracem	Jul 2	2	Jul 3	Terracem is complete; 2 nd lift of chip seal to be applied by mid-August
Twp 510 Terracem	Jul 4	5	Jul 10	Terracem is complete; 2 nd lift of chip seal to be applied by mid-August
Twp 512 Terracem	Jul 12	5	Jul 18	Terracem is complete; 1 st lift of chip seal to be applied by mid-August
Reg 191 Terracem	Jul 19	2	Jul 20	Terracem is complete; 1 st lift of chip seal to be applied by mid-August
Patching Oil	Jul 23	10	Aug 3	Expected completion by August 31
Oiling (TBD)	Aug 7	14	Aug 24	
Bridge Construction Rge 184, between Twp 494 and Twp 500	Aug 15	61	Oct 15	
Patching/Shoulder Pulls	Aug 28	24	Sep 30	
Backsloping- TBD	Oct 2	21	Oct 31	
Gravelling	Apr 24	112	Sep 28	
Dust Control- 1st Application	May 22	22	Jun 22	Complete
Dust Control- 2nd Application	Jul 30	14	Aug 18	

Schedule is subject to change depending on the weather.